

Stanley School Teddington, London



We were appointed by a design and build contractor to provide detailed information to submit to the local planning authority to satisfy landscape related conditions. Once these conditions were satisfied, we were appointed to provide construction information for a significant number of specific areas of the school site.

The site consisted of an existing school which was to remain open during term times. The works consisted of a number of structures are being demolished, a number of classroom blocks being built and the external spaces rationalised and enhanced in certain locations.

Due to the significant number of existing trees on site the planners were very interested in the specific construction details within the root protection zones of existing trees to be retained. Within the canopies of the existing trees, where possible, we proposed no dig construction. Where wooden decks were proposed we adopted principals which minimised the likely impact on the roots of the existing trees. We adopted a number of construction techniques to provide the desired surface finish whilst minimising the impact of construction on the existing trees.

The football pitch was remodelled to accommodate excess fill generated by site excavations. Some of this fill was contaminated and needed to be dealt with in an appropriate manner. We designed the remodelling of the football pitch so as to minimise the impact on existing structures, minimise the need for new structures and ensured that adequate circulation space surrounding the pitch was maintained.

Client
Jerram Falkus

Architect
Anshen and Allen Architects

15 Iliffe Yard | London | SE17 3QA | 020 7277 1035 | mail@davisla.com | www.davisla.com

Davis Landscape Architecture Limited
Registered in England and Wales
Company Number 07018870
VAT Registration Number 979558439

**Landscape
Institute**
Registered practice

Davis
Landscape Architecture